

## REMOVING AND REPLACING DRIVEWAY CULVERTS

### ITEM 18

WORK INCLUDED (Sec. 18.01) The Contractor shall, under Item 18, furnish all materials, tools and labor necessary for removing, cleaning and replacing driveway culverts encountered along the routes of the sewers, including the necessary excavation and backfilling.

DESCRIPTIONS (Sec. 18.02) All driveway culverts within the pay limits of the excavation for the main sewers, and such other as may be ordered by the Engineer, shall be carefully removed from the driveways ahead of the sewer excavation and stored temporarily during the construction of the sewer across driveways. After the sewer is built, and culvert pipes shall be cleaned, replaced in their original locations and backfilled as called for in Item 1.

If the Engineer determines that any culvert pipe is in such condition that it cannot be cleaned and reinstalled because of collapse, corrosion or for any other reason, it shall be replaced with new galvanized corrugated metal pipe as specified under item 31 or with new pipe equal to that type which it replaces.

PAYMENT (Sec. 18.03) The price for this item shall be included in prices for sewers under Items 8, 9, 10, 11, 12, 13, 14 or 15, as applicable and shall include all material, labor, tools and appliances required to accomplish this work.