

Ohio Residential Plan Submittal Form (Overhead Electrical Service)


Stark County Building Department

7235 Whipple Ave NW Ste A • Canton, Ohio 44720 • ph 330-451-1770 • fax 330-491-8373 buildingdept@starkcountyohio.gov

Address of Project	City	Project Description		
Contractor/DBA	Address	State License No	Phone No	Cell Phone No
Owner	Address	Phone No		Cell Phone No

Electrical Service Requirements

This information is not intended as a design specification or as an instruction for untrained persons.
NEC 110.3 All electrical equipment shall be installed and used in accordance with the listing requirements and manufacturer's instructions.
NEC 250.50 All grounding electrodes that are present at each building or structure served shall be bonded together to form the grounding electrode system. Conductor size per NEC 250.66. NEC 250.52 Permitted Electrodes include: 1. Metal underground water pipe in direct contact with earth for 10 feet or more 2. Metal frame of the building 3. Concrete-encased electrode 4. Rod, pipe & plate electrodes
NEC 230.66 Service equipment shall be marked to identify it as being suitable for use as service equipment.
NEC 230.70(A)(1) The service disconnecting means shall be installed at a readily accessible location.
NEC 230.70(A) Service disconnecting means shall not be installed in bathrooms. Including panel per NEC 240.24 .
NEC 230.71 & 230.72 The service disconnect shall consists of not more than six switches or six sets of circuit breakers. These switches or circuit breakers shall be grouped at one location.
NEC 230.79(C) The service disconnect shall have a rating of not less than 100 amperes.
NEC 230.85 Emergency Disconnects. For one and two family dwelling units, and emergency disconnecting means shall be installed. (A) General (1) Location. The disconnecting means shall be installed in a readily accessible outdoor location on or within sight of the dwelling unit.
NEC 230.90 & 230.91 Each ungrounded service conductor shall have overload protection. The service overcurrent device shall be an integral part of the service disconnecting means or shall be located immediately adjacent thereto.
NEC 310.16 and 310.15 (C) (1) wire ampacities.



I hereby do certify that all information given above is correct and accurate and has been included as part of the submitted plans.

PRINTED NAME (Owner/Applicant) _____ TITLE _____

SIGNATURE _____ DATE _____